KADUR DIVISION.

Notification dated 15th February 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 10th March 1933, for Reconstructing the damaged bridge at 5—17th mile of Tarikere-Mangalore Road. An approximate estimate of quantities with rates is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees sixty only in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Reconstructing the damaged bridge at 5—17th mile of Tarikere-Mangalore Road," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each and every item.

10. Percentage quotations either below the lowest tender or below the estimated rates will not be accepted.

11. In all matters of dispute regarding quality of work or rates, the decision of the Superintending Engineer, Shimoga Circle, is final and legally binding.

12. No claims of enhanced rates should be preferred after the acceptance of tender or at any time during execution of work.

13. For Lumpsum items and also items found necessary during execution rates as per current schedule rates or at tendered rates for such of the items as form a portion in lumpsum provision or as per data worked out and approved by the Superintending Engineer, Shimoga Circle, will be allowed.

14. No representations regarding rates, etc., from the rejected tenderers will be considered.

15. The contractor shall hold himself responsible for good behaviour of his employees of all grades.

Estimate for reconstructing the damaged bridge at 5—17th mile of Tarikere-Mangalore Road.

No.	Items of work	Unit	Rate	Quantity	Rates tendered	
					In figures	In words
			Rs. a. p.			
1	Removing metal and earthen cushion	C.yd.	0 4 0	60		
2	Dismantling and removing damaged timber covering, etc.	C.ft.	0 1 0	351		
3	Dismantling and removing rough stone masonry works.	„	0 0 4	1896		
4	Earthwork excavation foundation ...	C.yd.	0 4 0	82		
5	Stone jelly concrete in surki mortar...	C.ft.	0 6 0	365		
6	Size stone in surki mortar ..	„	0 8 0	1565		
7	Old stone in do ..	„	0 3 6	948		
8	Burnt stone slabs 6" thick dressed and fixed in surki mortar.	S.ft.	1 4 0	76		
9	Pointing with do	Sqr.	3 8 0	5·07		
10	Providing new R. S. girders 12" x 6" x 44 lbs. including Railway frieght	Cwt.	13 0 0	28·30		
11	Carting, hoisting and boxing charges	L. S.	...	...		
12	Surki concrete coping ($1\frac{1}{2}$' x $\frac{3}{4}$') over parapets including plastering	Rft.	0 6 0	38		

No.	Items of work	Unit	Rate	Quantity	Rates tendered	
					In figures	In words
			Rs. a. p.			
13	Jungle wood cover planks 6" thick with available good old scantlings and new iron bolts and nuts etc., complete.	C.ft.	0 8 0	93		
14	New jungle wood planks 6" thick including iron bolts etc., complete.	,,	3 8 0	81		
15	Tarring or Bhadra painting to wood work and girders.	Sqr.	3 0 0	8·46		
16	Providing 1½" galvanized pipe railings with iron uprights etc., complete	L. S.	...	...		
17	Rough stone work new	C.yd.	2 8 0	55		
18	Earthwork filling and forming roadway including watering and tamping.	,,	0 5 0	238		
19	Metalling the roadway including consolidation with metal and gravels	S.yd.	0 3 0	80		
20	Forming a duration road including earthwork clearing water way, cutting and forming in stony soil jungle clearing etc., complete.	L. S.	...	...		
21	Barricading, lighting, watchmen, tmeporary shed etc.	L. S.	...	..		

L. A. H. WINCKLER,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE EXCISE COMMISSIONER IN MYSORE, BANGALORE.

(Notice No. C1-78-32, dated 15th February 1933.

The undermentioned articles will be sold by public auction at 2-30 P.M., on Monday, the 27th February 1933 at the New Public Offices, Bangalore.

2. The articles are open for inspection at the Excise Commissioner's Office Stores in the New Public Offices, on working days between the hours 11 A.M., and 5 P.M.

3. The sale conducting officer may, at his discretion, refuse to accept the bid of any person without assigning any reason therefor.

4. The person in whose favour any article is knocked down, shall pay the full amount of the bid value immediately and make his own arrangements for its removal.

5. In case the person, whose bid is accepted, fails to pay the full amount, the article will be resold immediately at the risk of the original purchaser.

Sl. No.	Names of articles.	Quantity	Remarks
1	"Big-Ben" Time-piece (old)	1	
2	Old pattern brass buttons	193	
3	Khaki mull pieces 18, measuring	41¾ yds.	
4	do 1, do	122½ yds.	
5	Copper gallon-pots	2	
6	Sample paints, small tins	50	
7	Sandals singles	3	
8	Boots, singles	1	
9	Brass cocks	30	
10	Old locks	10	with a bunch of keys.

G. RUDRAPPA,
For *Excise Commissioner.*